

SPECS BY LOCATION/TRADE

8/6/2010

Work Write-up/Re-Bid: _____
 Walk-Through Date: _____
 Bid Date: _____
 Initial: _____

Case Number: _____
 Construction Specialist: _____
 Phone: _____

Address: 1513 Root Street **Unit:** Unit 01

Location: 1 - General Requirements Approx. Wall SF: 0 Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 1 General Requirements

120	Remove construction debris Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work areas, removing all visible dust, stains, labels and tags. Clean all windows referenced in specifications.	1.00	RM	_____	_____
37	ELECTRICAL PERMIT REQUIRED Prior to the start of work, the contractor shall create any documentation necessary to apply for, pay for and receive an electrical permit on behalf of the owner.	1.00	EA	_____	_____
38	PLUMBING PERMIT REQUIRED Prior to the start of work, the contractor shall: create a riser diagram, septic layout and all other documentation needed to apply for, pay for and receive a plumbing permit on behalf of the owner.	1.00	EA	_____	_____
39	HVAC PERMIT REQUIRED Prior to the start of the heating/cooling work, the contractor shall create a heating distribution layout and perform heat/cooling loss calculations and all other documentation needed to apply for, pay for and receive an HVAC permit on behalf of the owner.	1.00	EA	_____	_____

Trade: 9 Environmental Rehab

9044	BID & PERFORMANCE BONDS Purchase from an United States Surety approved by the U.S. Treasury Department, performance and payment bonds using the ABC or AIA form in an amount of 100% of the contract sum.	1.00	M	_____	_____
------	---	------	---	-------	-------

Bidder: _____

Location Total: _____

Location: 2 - Interior Approx. Wall SF: 0 Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 19 Paint & Wallpaper

5566	PREP & PAINT HOUSE (INTERIOR) Remove/cover all hardware, fixtures not to be painted. Wet scrape loose, cracked, peeling, blistered surfaces. Feather edges & dull gloss surfaces with sandpaper. Clean all surfaces. Spot prime and top coat trim, ceiling, walls, doors & windows with owner's choice of premixed latex. Include any closets.	1,560.00	SF	_____	_____
------	--	----------	----	-------	-------

Address: 1513 Root Street

Unit: Unit 01

Location: 2 - Interior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 20 Floor Coverings					
5930	UNDERLAY & VINYL SHEET GOODS Install 1/4" underlayment , using 7d screw shank or cement coated nails, or narrow crown staples, 6" on center allowing a 1/4" gap at wall. Install 070" thick, backed vinyl sheet goods w/ minimum seams, per manufact. recommendations. Caulk edges of vinyl w/clear silicone caulk to create positive seal. Install metal edge strips in openings & shoe molding. \$15 material allowance for vinyl. Kitchen, Laundry, 1/2 Bath, Foyer	125.00	SF	_____	_____
5960	REMOVE FLOOR COVERING TO SUBFLOOR Remove floor covering to subfloor, remove all staples/nails, inspect subfloor for water/mold damage. Remove all transitions. Downstairs only. Leave carpet on stairs.	780.00	SF	_____	_____
5963	CARPET--STEAM CLEAN Steam clean existing carpets All upstairs carpet	700.00	SF	_____	_____

Trade: 21 HVAC

6145	DUCT CLEANING Subcontract a certified duct cleaning company to remove grates and use a truck mounted cleaning system to remove all dust and particles from HVAC system. Provide written certificate at time of check request.	1,560.00	SF	_____	_____
------	---	----------	----	-------	-------

Trade: 23 Electric

7810	SMOKE DETECTOR--HARD WIRED Install a UL approved, ceiling mounted smoke and heat detector permanently wired into a receptacle box. House is already wired. Replace units only	6.00	EA	_____	_____
------	--	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 3 - Kitchen

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 10 Carpentry					
3715	CABINET--WOOD BASE Replace base cabinets. Install base cabinet with doors of solid birch or ash stiles and veneered plywood panels. Frame with solid birch or ash stiles, 1/4" veneered plywood sides and metal or plastic corner bracing. Drawers shall be made of wood or composition material. Owner's choice of two in-stock designs. Leave spot for dishwasher	10.00	LF	_____	_____
3725	CABINET--WOOD WALL	12.00	LF	_____	_____

Address: 1513 Root Street

Unit: Unit 01

Location: 3 - Kitchen

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

Replace wall cabinets. Field measure and screw to studs, level and plumb, kitchen wall cabinet. Door to have solid wood stiles and plywood panels. Frame to have solid wood stiles, 1/4" plywood sides, metal or plastic corner bracing.

3750	COUNTER TOP--PLASTIC LAMINATE Dispose of counter top. Field measure and manufacture a plastic laminate counter top, glued to particle board designed for this purpose. Provide cutout for sink. Owner's choice of in-stock color and texture.	14.00	LF	_____	_____
------	---	-------	----	-------	-------

Trade: 21 HVAC

6330	REGISTER COVER--REPLACE Replace missing or damaged register cover with an adjustable metal register.	1.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 22 Plumbing

6815	FAUCET--KITCHEN DUAL CONTROL Install a metal kitchen sink faucet with spray, dual controls, 15 year drip-free warranty and maximum flow of 2 gallons per minute.	1.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 23 Electric

7560	RECEPTACLE REPLACE Replace receptacle with ivory duplex receptacle and ivory metal cover plate.	4.00	EA	_____	_____
------	---	------	----	-------	-------

7595	RECEPTACLE--GFCI COUNTERTOP 15 AMP Install a flush mounted, ground fault circuit interrupted, ivory, duplex receptacle and ivory cover plate using #14 copper romex, controlled by a 15 amp circuit breaker. Fish wire and repair all tear out.	1.00	EA	_____	_____
------	---	------	----	-------	-------

7675	SWITCH REPLACE Replace light switch with single pole, ivory toggle switch and ivory metal cover plate. Use plastic cover plates in bath area.	1.00	EA	_____	_____
------	---	------	----	-------	-------

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

7840	RANGE HOOD--RECIRCULATING Install a 30", recirculating, enameled metal range hood with light, charcoal filter, and washable grease filter. Owner's choice of color.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 4 - Laundry

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Address: 1513 Root Street

Unit: Unit 01

Location: 4 - Laundry

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 21 HVAC

6415	Replace cover for washer box Find a cover for the plastic box which houses the washer connections	1.00	EA	_____	_____
------	---	------	----	-------	-------

Trade: 23 Electric

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 5 - Living Room

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

2525	HAND RAIL WITH BALUSTERS Replace portion of mantle destroyed by vandals, match existing, prime and paint	3.00	LF	_____	_____
------	--	------	----	-------	-------

Trade: 18 Ceramic Tile

5425	CERAMIC FLOOR TILE Using adhesive, lay owner's choice of \$3/sf ceramic floor tile over 1/2" reinforced cement board, screwed to subfloor. After at least 24 hours drying time, apply latex- portland grout. Clean floor and apply mildew resistant white silicone caulk to all edge seams and pipe penetrations. Install a 3" marble threshold at door. Install around new gas fireplace, match existing	12.00	SF	_____	_____
------	--	-------	----	-------	-------

Trade: 20 Floor Coverings

5970	CARPET AND PAD Install FHA approved, nylon, plush carpet over a 1/2" medium density rebond pad w/ a minimum of seams. Stretch carpet to eliminate puckers, scallops & ripples. Include tackless strips, metal edge strips, and mending tape to cover entire floor including closets. On stairs, fasten carpet and pad at top and bottom of each riser. Carpet and pad material allowance \$20/sy. Owner's choice of in stockcolor and pattern.	47.00	SY	_____	_____
------	--	-------	----	-------	-------

Trade: 21 HVAC

6085	HEATER 25,000 BTU GAS WALL Install a 25,000 BTU wall mounted gas heater including all gas line, thermostat, flue piping and grills to provide a complete and code compliant installation. Replace stolen fireplace	1.00	EA	_____	_____
------	---	------	----	-------	-------

Address: 1513 Root Street

Unit: Unit 01

Location: 5 - Living Room

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 21 HVAC

6330	REGISTER COVER--REPLACE Replace missing or damaged register cover with an adjustable metal register.	2.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 23 Electric

7560	RECEPTACLE REPLACE Replace receptacle with ivory duplex receptacle and ivory metal cover plate.	4.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 6 - 1/2 Bath

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

3810	TOWEL BAR Install a 16" chrome plated steel towel bar, screwed securely to studs.	1.00	EA	_____	_____
------	---	------	----	-------	-------

3825	BATHROOM MIRROR MATCH SIZE WITH VANITY, WALLMOUNT	1.00	EA	_____	_____
------	---	------	----	-------	-------

Trade: 22 Plumbing

6901	VANITY--30" COMPLETE Install a 30" vanity complete with plywood cabinet, cultured marble top, dual control, brass bodied, single lever faucet, supply risers, shut-off valves and all required waste connectors to complete the installation.	1.00	EA	_____	_____
------	---	------	----	-------	-------

7010	COMMODE--REPLACE--1.6 GPF--GCI Install a 2 piece, close coupled, white, vitreous china, commode with a maximum water usage per flush of 1.6 Gallons. Include plastic or pressed wood white seat, supply pipe, shut-off valve, flap valve and wax seal.	1.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 23 Electric

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 7 - Foyer

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

Address: 1513 Root Street

Unit: Unit 01

Location: 7 - Foyer

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

2407	CASING--COLONIAL 2 1/4" Install finger jointed WM-626fj 9/16" x 2-1/4" colonial CASINGE with finish nails of sufficient length to penetrate framing 1". Mitre all lap joints, and break all lap joints over framing. INSTALL TO FRONT DOOR AND GARAGE ENTRY DOOR	40.00	LF	_____	_____
------	---	-------	----	-------	-------

3275	PASSAGE LOCK Install a brass plated, 2-1/2" back set door knob set. LAUNDRY ROOM, FOYER CLOSET, BASEMENT DOOR	4.00	EA	_____	_____
------	--	------	----	-------	-------

3280	LOCKSET--BEDROOM Install a back set, brass plated privacy lock set. GARAGE DOOR, 3 BEDROOMS, MASTER BATH, MAIN BATH,	6.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 8 - Garage

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

3360	GARAGE DOOR OPENER INSTALL A 1/2 HP SCREW DRIVE OPENER WITH 2 REMOTES	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 9 - Stairway

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

2520	HANDRAIL--REPLACE INTERIOR Install 2" round hardwood handrail with braces screwed to studs and handrail.	12.00	LF	_____	_____
------	--	-------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 10 - Bathroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

3285	LOCKSET--BATHROOM Install a back set, privacy lockset with a brass plated exterior knob and a chrome plated interior knob.	1.00	EA	_____	_____
------	--	------	----	-------	-------

3810	TOWEL BAR Install a 16" chrome plated steel towel bar, screwed securely to	2.00	EA	_____	_____
------	--	------	----	-------	-------

Address: 1513 Root Street

Unit: Unit 01

Location: 10 - Bathroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

studs.

3825	VANITY MIRROR INSTALL A 48" WIDE MIRROR OVER VANITY	1.00	EA	_____	_____
------	---	------	----	-------	-------

Trade: 20 Floor Coverings

5920	TRANSITION STRIP INSTALL A METAL TRANSITION STRIP BETWEEN BATHROOM AND HALL INCLUDE MASTER BED, & MASTER BATH	9.00	SF	_____	_____
------	--	------	----	-------	-------

Trade: 22 Plumbing

6870	FAUCET--LAVATORY DUAL CONTROL Install a washerless, metal bodied, dual control faucet with a 15 year drip-free warranty. Include shut-off valve. Replace trap if required to complete installation.	1.00	EA	_____	_____
------	---	------	----	-------	-------

6875	VANITY TOP INSTALL 48" VANITY TOP, CULTURED MARBLE, MATCH EXISTING	1.00	EA	_____	_____
------	--	------	----	-------	-------

6935	SHOWER HEAD--2 GPM--GCI Install a chrome plated brass shower head with a maximum 2.0 gallons per minute flow rate. Include arm where required. Note: any low-flow showerhead should be controlled by a valve that has been designed, tested, and verified to function safely at the reduced flow rate.	1.00	EA	_____	_____
------	---	------	----	-------	-------

7010	COMMODE--REPLACE--1.6 GPF--GCI Install a 2 piece, close coupled, white, vitreous china, commode with a maximum water usage per flush of 1.6 Gallons. Include plastic or pressed wood white seat, supply pipe, shut-off valve, flap valve and wax seal.	1.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 23 Electric

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 11 - Hall (Upstairs)

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

2525	HAND RAIL WITH BALUSTERS Install oak handrail and newel post, and pine turned balusters 6" on center.	5.00	LF	_____	_____
------	---	------	----	-------	-------

Address: 1513 Root Street

Unit: Unit 01

Location: 11 - Hall (Upstairs)

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 10 Carpentry					

Trade: 23 Electric

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 12 - S.W. Bedroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 10 Carpentry					

4015	CLOSET SHELF INSTALL METAL SHELVING, MATCH EXISTING INCLUDE ALL BEDROOMS	30.00	LF	_____	_____
------	---	-------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 13 - Master Bedroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 23 Electric					

7730	LIGHT FIXTURE--REPLACE Replace a ceiling mounted, 2 bulb, UL approved, incandescent light fixture with shade and lamps. \$30 allowance for fixture.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 14 - Master Bathroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 22 Plumbing					

6635	SUPPLY--COPPER Install type L rigid copper supply lines to fixtures with silver/tin solder. No solder containing lead is allowed. Install 3/4" pipe to branches and provide shut off valves at all fixtures. Provide dielectric unions at iron pipe joints. REPLACE STOLEN COPPER UNDER BOTH SINKS, REPLACE TOILET SUPPLY LINE	10.00	LF	_____	_____
------	--	-------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 16 - Basement

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Location: 16 - Basement

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 7 Masonry					
1185	GLASS BLOCK WINDOW Replace old basement window with premade glass block unit with 6"x 6"x 4" thick glass block. At least two windows on opposite sides of room should have operable vent.	1.00	EA	_____	_____
Trade: 8 Metal Work					
1495	SECURE STANCHIONS TO METAL BEAM Attack stanchions in basement to metal support beam. Either weld or use machanical fasteners.	2.00	EA	_____	_____
Trade: 21 HVAC					
6041	FURNACE 90+ GAS - REPLACE--GCI Use the Air Conditioning Contractors of America (ACCA) 8th Edition of their Manual J Heat loss calculation tool http://www.acca.org/tech/manualj/ (calculate manual J based on the post rehab building envelope), and use ACCA's Manual S for equipment selection. NOTE: Provide both Manual J & S reports with first Draw documents. Size furnace to the living unit considering any areas which may be added or subtracted from the plan. Remove existing furnace, recycle all metal components and dispose of all other materials in a code legal dump. FURNACE: install a 90+ gas fired forced air furnace with minimum AFUE rating of 90% on 2" patio block to existing duct work & gas line. New furnace to be vented with PVC piping per manufacturer's specifications. New furnace will have minimum limited warranties of: 20 years on heat exchangers; 5 years on parts. Include auto set back thermostat controls, vent pipe & new shut-off valve. Rework cold air return if necessary to ensure easy access, good fit & easy replacement of air filter. An exterior return air filter box shall be installed on one side, both sides, or bottom of new furnace. Seal all exposed duct joints as a part of this item with Duct Mastic. Remove all existing cloth duct tape prior to installing mastic.	1.00	EA	_____	_____
6185	A/C--REPLACE CENTRAL UNIT Submit manuf cut sheet & cooling load calc for proposed equip to owner at least 15 working days prior to install. Remove existing A/C equip to legal dump. Install cent A/C sys w/ min EER of 8.6, inc condensing unit, A type evaporator coils, control & power wiring, insulated freon lines, plenums, ext pad & necessary connections to create complete install. Provide owner w/factory warranty, manual, & 1 yr contractor warranty.	1.00	EA	_____	_____
Trade: 22 Plumbing					
6630	SUPPLY--PEX Install flexible pex piping with a minimum number of couplings to fixtures. Install mechanical connectors and shut off valves at all fixtures. Size pipe to 1990 CABO minimums per table 2406.5.	150.00	LF	_____	_____

Address: 1513 Root Street

Unit: Unit 01

Location: 16 - Basement

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 22 Plumbing

7071	HWH - 90+ 40 GAL GAS POWER VENTED--GCI Install a 40 gallon, glass lined, 90+ efficient power vented, insulated to R-7, gas water heater with a 10 year warranty. Include pressure & temperature relief valve, discharge tube to within 6" of floor, condensate pump, owners manual & all duct work to power vent to exterior. Provide separate electrical circuit & new gas piping from shut-off valve to fixture. Dispose of old water heater in code legal dump. If the HWH is located in a basement with a floor drain the discharge tube shall be directed to the drain. If it is located on an upper floor or if there is no floor drain, install a catch pan drained to the exterior. Recycle the existing HWH.	1.00	EA	_____	_____
7140	REPAIR INLET WATER LINE CHISEL CONCRETE AWAY FROM INLET WATER LINE (ENOUGH TO GET FITTING ON) AND RE-IN STALL THE WATER METER	1.00	EA	_____	_____
7145	SUMP PUMP COMPLETE Install a 1/3 horse power, submersible sump pump and repair discharge piping (include check valve).	1.00	EA	_____	_____

Trade: 23 Electric

7465	REPLACE STOLEN WIRING IN BASEMENT REPLACE WIRING STOLEN BY VANDALS. USE PROPER SIZE FOR CODE, REATTACH TO EXISTING BREAKER BOX.	1.00	EA	_____	_____
------	---	------	----	-------	-------

Bidder: _____

Location Total: _____

Location: 17 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

2640	SIDING---VINYL REPAIR Hang vinyl siding including all cornice, corner, door and window trim after replacing all deteriorated exterior building components. Wrap home with 1/4 inch fan fold insulation and apply owner's choice of siding color, exposure and texture with 50 year warranty. REPLACE CORNER PIECE & REPAIR DAMAGED SECTIONS	0.50	SQ	_____	_____
2841	DOOR TRIM REPLACE COLONIAL TRIM AROUND EXTERIOR OF FRONT DOOR, MATCH EXISTING	1.00	EA	_____	_____
2980	WINDOW--VINYL Singlee HNG DBL GLZ Field measure, order and install a vinyl, single hung, double glazed, one-over-one window and jamb including screen, caulk, interior casing and exterior trim. Install half screen. MASTER BEDROOM, INCLUDE GRILLS	1.00	EA	_____	_____

Address: 1513 Root Street

Unit: Unit 01

Location: 17 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 10 Carpentry

3010	REPLACE GLASS IN EXISTING SASH REPLACE DOUBLE PANE GLASS IN BROKEN WINDOWS, RE-USE EXISTING SASHES INCLUDE GRILLS	3.00	EA	_____	_____
------	---	------	----	-------	-------

3185	DOOR--PREHUNG METAL ENTRANCE Dispose of door and frame. Install a prehung metal, insulated, 6-panel entrance door and jamb including interior and exterior casing, spring metal weatherstripping, interlocking threshold, one entrance and one mortised deadbolt keyed alike. Prime and top coat. REPLACE FRONT DOOR AND REINSTALL GARAGE ENTRY DOOR (FROM FOYER)	1.00	EA	_____	_____
------	---	------	----	-------	-------

3187	DOOR--SLIDING GLASS UNIT Dispose of door and frame. Install a prehung vinyl, insulated,sliding door and jamb unit, including interior and exterior casing, weatherstripping, threshold, and locking hardware.	1.00	EA	_____	_____
------	--	------	----	-------	-------

Trade: 15 Roofing

4635	GUTTER--5" SEAMLESS ALUMINUM Dispose of gutter. Install 5", K- type, seamless, .027 gauge aluminum gutter to service roof. White or brown color choice by owner.	25.00	LF	_____	_____
------	--	-------	----	-------	-------

4640	DOWNSPOUT--5" SEAMLESS ALUMINUM Dispose of downspout. Install 5", square, seamless, .027 gauge, white, aluminum downspout.Strap at least 3' on center. REPLACE WHERE MISSING	50.00	LF	_____	_____
------	--	-------	----	-------	-------

4755	REPLACE ALUMINUM FASCIA INSTALL 6" ALUMINUM FASCIA WHERE MISSING	20.00	LF	_____	_____
------	--	-------	----	-------	-------

Bidder: _____

Location Total: _____

Unit Total for 1513 Root Street, Unit Unit 01: _____

Address Grand Total for 1513 Root Street: _____